

GOVERNMENT OF TELANGANA
ABSTRACT

Irrigation & CAD Department - SRSP – Stage-I – Water release for drinking needs below LMD -Orders – Issued.

=====

IRRIGATION AND CAD (Projects-II) DEPARTMENT

G.O.Rt.No.316

Dated:13-05-2015

Read:-

From the Administrator-cum-Chief Engineer, Sriramsagar Project,
Hyderabad Lr.No.ACE/SRSP-1/DEE-1/AEE-1/ District Profile/2014-15/
383, Dt:31.03.2015.&&&

&&&

ORDER:-

In the circumstances reported by the Administrator-cum-Chief Engineer, Sriramsagar Project, Hyderabad in the reference read above, Government after careful examination of the proposal hereby accord permission to the Administrator-cum-Chief Engineer, Sriramsagar Project, Hyderabad to utilize the available water only for drinking needs as follows:

Sriramsagar Project water requirement up to 31st July 2015 (above LMD)

STATUS OF RESERVOIR LEVEL IN SRSP							
Sl.No.	Description	Upto 31.03.2015	Apr-15	May-15	Jun-15	Jul-15	Remarks
	Opening Balance in TMC	-	13.7	12.18	10.87	10.29	
I	Evaporation losses						
1.	Average evaporation factor	-	0.03	0.03	0.024	0.018	
2.	Average contour area	-	1107.22	840.41	797.66	755.20	
3.	Quantity in TMC during the month (Evaporation losses)	-	0.997	0.782	0.574	0.421	
II	Drinking water requirement	-					
1.	Nirmal Municipality	-	0.005	0.005	0.005	0.005	
2.	Jalalpur Drinking water scheme	-	0.01	0.01	0.01	0.01	
3.	Metpally, Korutla & Jagithyal Municipalities	-	0.5 (15 th)	0.5 (30 th)	-	0.5 (15 th)	
4.	Nirmal CPW Schemes	-	0.01	0.01	0.01	0.01	
5.	Feeding tanks under Laxmi Canal	-	0	0	0	0	
6.	Feeding tanks under command area of saraswathi canal.	-	0	0	0	0	
7.	L.I. Scheme of Adilabad (16) & Nizamabad (15) District.	-	0	0	0	0	
8.	Alisagar & Guthpa L.I. Schemes	-	0	0	0	0	
III	Consumption as on end of the month	-	1.522	1.307	0.599	0.446	
1.	Net Quantity balance in Reservoir in TMC	13.70	12.18	10.87	10.29	9.38	
2.	Corresponding Reservoir level at end of the Month	1060.10	1058.60	1057.10	1056.30	1055.10	

P.T.O.

LMD Water requirement (Below LMD)

STATUS OF RESERVOIR LEVEL IN LMDAM							
Sl.No.	Description	Upto 31.03.2015	Arp-15	May-15	Jun-15	Jul-15	Remarks
	Opening Balance in TMC	-	5.659	3.671	3.305	3.016	
I	Evaporation losses						
3.	Quantity in TMC during the month (Evaporation losses)	-	0.294	0.224	0.152	0.053	
II	Drinking water requirement	-					
1.	Karimnagar Municipality (35 Cusec)	-	0.091	0.094	0.091	0.045	
2.	Siddipet Drinking water scheme (8 Cusec)	-	0.021	0.021	0.021	0.010	
3.	Sircilla Drinking water scheme (8 Cusec)	-	0.021	0.021	0.021	0.010	
4.	Vemulawada Drinking water scheme (2 Cusec)	-	0.005	0.005	0.005	0.003	
5.	Supply to Warangal and Nalgonda area through canal for 9 days @ 2000 Cusec	-	1.555	0	0	0	
III	Consumption as on end of the month	-	1.988	0.366	0.289	0.122	
1.	Net Quantity balance in Reservoir in TMC	5.659	3.671	3.305	3.016	2.894	
2.	Corresponding Reservoir level at end of the month	889.05	882.45	881.00	879.70	879.15	

2. The Administrator-cum-Chief Engineer, Sriramsagar Project, Hyderabad is requested to take necessary action as per the Government rules and codes.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF TELANGANA)

**SHAILENDRA KUMAR JOSHI
PRINCIPAL SECRETARY TO GOVERNMENT**

To
The Administrator-cum-Chief Engineer, SRSP, Hyderabad.

// FORWARDED : : BY ORDER //

SECTION OFFICER